

650 FLOOR FINISHES SCHEDULE ID PRODUCT EUROPEAN CERAMICS, PORTRAITS COMBLANCHIEN NATURAL 2780 x 1195 x 6MM, GROUT: ARDEX FG8 '241 MISTY BELGOTEX. CULTURES. '44 WELLESLEY WAVE'. RF52953606-R RECOLOURED FREEDOM STRATEGIES. TREADMASTER MAXI STEP 2 (TMMS2). ALUMINIUM: SILVER. CARPET: CHARCOAL110 BELGOTEX, BIOSPEC 'BASIC BLACK 15383' FC-04 BELGOTEX. GRANITE 'MORNING FOG' 500X500 CARPET TILE. INSTALLATION: RANDOM BELGOTEX, SMOOTH 'AGGREGATE' 250X1000 CARPET PLANK. INSTALLATION: HERRINGBONE BELGOTEX. MATRIX ACOUSTIC 'RIVIERA OAK 1240'. INSTALLATION: HERRINGBONE FC-07 FC-02 & FC-04 SPEC FC-05 & FC-06 SPEC REVISED

NOTES:

-TILER TO ENSURE A CAVITY FREE INSTALLATION. THERE MUSTN'T BE ANY GAPS BETWEEN THE TILE AND THE SUBSTRATE.

-TILER NEEDS TO FULLY COVER THE TILE WITH ADHESIVE AND NOT SPOT FIX THE MATERIAL

-IT IS VITAL TO ENSURE THAT THE FLOOR IS LEVEL BEFORE INSTALLATION.

01 650 MOCK-UP OFFICE PROPOSED FLOOR FINISHES PLAN (LVL 6)

1:100

	ISSUE	DRAWN:Author CHKD:Check		_	NOTES	DATE:		REVISION	DATE	DESCRIPTION	PROJECT NO:	DRAWING NO:
Y6	50D 00N6	TDUIGTION			DO NOT SCALE FROM THIS DRAWING, FIRSTLY CHECK ALL DIMENSIONS, CLEARANCES & ACCESS SIZES ON SITE PRIOR TO CONSTRUCTION.		LOBBY & OFFICE REFURB	A B	08.10.19 21.10.19	UPDATES TO TENDER DRAWINGS REVISED FLOOR FINISHES	6703	651
	FOR CONS	STRUCTION	(_/	,)	THE BUILDER IS RESPONSIBLE FOR THE SETTING OUT OF THE WORKS, THE CHECKING OF ALL DIMENSIONS AND LEVELS ON SITE, AND THE REPORTING OF ANY DISCREPANCIES TO THE		44 WELLESLEY ST WEST, AUCKLAND CP GROUP				SCALE @ A3	REVISION:
1 CENTRE STREET , AUCKLAND CENTRAL PO BOX 91112 AUCKLAND 1142 WWW.YELLOW6.CO.NZ	0 1 2	3 4m 1:100	$\neg \lor$		ARCHITECT PRIOR TO COMMENCEMENT OF WORK WORKS TO COMPLY WITH NZBC & NZ STANDARDS COPYRIGHT OF THIS DRAWING AND DESIGN REMAINS THE PROPERTY OF YELLOW 6 DESIGN.	1	MOCK-JUP OFFICE PROPOSED FLOOR FINISHES PLAN (LVL 6)				1 : 100	В